BRUHAT BANGALORE MAHANAGARA PALIKE

Name of Work: Community Property Maintenance (Including Parks) in JP Park in Ward No.17

Estimate Cost: 5.00 Lakhs
Schedule-B Cost: 4,02,388 Lakhs
Tender Premium: 4.08% Below

FORM PWG - 91
FORM OF EXTRA ITEM RATE LIST (EIRL)

Sl. No.	Item of work	Unit	Approximate Qty	Rate including T.P	Amount	Whether the items are alternative to items in the Tender of whether they are additional items	Whether the extra items included in the sanctioned estimate	How the extra cost of the item is proposed to be met	Whether the extra item is inculded in the schedule of rates of the Division, if so reference to schedule to be given, if not Data sheet accompanying the rates list	Remarks
1	2	3	4	5	6	7	8	9	10	11
1	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) (P. 27, It.No.5.33	Sqm	95.04	106.76	10146.00	Additional items	No	In over all savings of the estimate	Rate Analysis enclosed	
2	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P. 143, It.No.19.1)	Cum	105.60	132.18	13958.00	Additional items	No	In over all savings of the estimate	Rate Analysis enclosed	
3	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm (P. 27, It.No.5.26.1)	Sqm	140.80	978.12	137719.00	Additional items	No	In over all savings of the estimate	Rate Analysis enclosed	
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. - do - 10 cms thick (P. 27, It.No.5.31.2)	Sqm	63.36	927.28	58752.00	Additional items	No	In over all savings of the estimate	Rate Analysis enclosed	
5	KSRB 5-9 : Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 (P. 26, It.No.5.22)	Rmt	440.00	58.97	25948.00	Additional items	No	In over all savings of the estimate	Rate Analysis enclosed	
6	KSRB 5-8.1 : Providing one line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5.1.13 (P. 26, It.No.5.17)	Sqm	158.40	912.03	144465.00	Additional items	No	In over all savings of the estimate	Rate Analysis enclosed	

Scanned with CamScanner

Sl. No.	Item of work	Unit	Approximate Qty	Rate including T.P	Amount	Whether the items are alternative to items in the Tender of whether they are additional items	Whether the extra items included in the sanctioned estimate	How the extra cost of the item is proposed to be met	Whether the extra item is inculded in the schedule of rates of the Division, if so reference to schedule to be given, if not Data sheet accompanying the rates list	Remarks
1	2	3	4	5	6	7	8	9	10	11
7	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (P. 136, It.No.17.1)	Cum	105.60	97.00	10243.00	Additional items	No	In over all savings of the estimate	Rate Analysis enclosed	
	Total				401231.00					

The EIRL Amounting to Rs. 244944 (Rupees Two Lakhs Fourty Four Thousand Ninex Hundred and Fourty Four only) is hereby recommended for Approval.

Amount as per BOQ	402388
Amount as per EIRL	401231
% of savings over the sanctioned estimate	99.71%

Assistant Engineer
Ward No.17

Assistant Executive Engineer
Yeshwanthapura Sub Division

Executive Engineer
RR Nagara Division, RR Nagara Zone

Rates are hereby Approved

"Here by EIRL amount Rs: 4,01,231/-
[Rs four Lakhs one thousand two hundred thirty one only] i's approved"

Chief Engineer
RR Nagara Zone, BBMP

ಮುಖ್ಯ ಅಧಿಯಂತರರ
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಲಯ
ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Scanned with CamScanner